ADDENDUM NO. 2

CITY OF CARTERSVILLE, GEORGIA

Mechanicsville & Jones Mill Rd. Water Main Replacement

BID DATE: November 12, 2026
TIME: 3:00 P.M.

Date: November 5, 2026

THIS ADDENDUM FORMS A PART OF THE PROJECT DOCUMENTS. IT MODIFIES THEM AS FOLLOWS:

PLEASE MAKE CHANGES TO THE FOLLOWING CONTRACT DOUMENTS:

SECTION 00410 BID FORM: Delete this section and replace it with new SECTION 00410 BID FORM attached.

QUESTION:

1. There are two connections to existing 8" water mains shown on C-316 for Phase II. The bid form for phase II only shows the 6" connection on sheet C-321. Can an item be added for connecting to existing 8" water main?

   Response: Added a new line item (10. Connect to to Exist. 8" Water Main) to the Phae II Bid Form. See attached revised Section 00410 BID FORM.

2. We noticed that the measurement and payment section states that payment for thrust blocking will not be paid for under the individual water main pipe items. Should thrust blocking related to fittings and bends be associated with the cast iron special bid items?

   Response: Pipe will be restrained at the joints as called out for in the plans. No additional restraint shall be required.

3. Can the Milling and 12.5mm quantities be double checked? We are coming up with way less quantities here.

   Response: GMC reviewed the milling and asphalt quantities and have found them to be close to the bid form item quantities. Keep in mind this project is a unit price project, and Contractor will be paid on how much you have installed.

END OF ADDENDUM NO. 2

SECTION 00410
BID FORM

TABLE OF ARTICLES

Article No. Page No.

ARTICLE 1 – BID RECIPIENT 2

ARTICLE 2 – BIDDER'S ACKNOWLEDGMENTS 2

ARTICLE 3 – BIDDER'S REPRESENTATIONS 2

ARTICLE 4 – FURTHER REPRESENTATIONS 4

ARTICLE 5 – BASIS OF BID 4

ARTICLE 6 – TIME OF COMPLETION 7

ARTICLE 7 – ATTACHMENTS TO THIS BID 7

ARTICLE 8 – DEFINED TERMS 7

ARTICLE 9 – BID SUBMITTAL 7

ARTICLE 1 – BID RECIPIENT

1.01 BID RECIPIENT

This Bid is submitted to: City of Cartersville

301 Douthit Ferry Road

Cartersville, GA 30120

This Bid is Submitted From: _____

_____

_____

Cell Phone: _____

(Name, Address and Cell Phone Contact of Individual, Partnership, or Corporation)

_____

Georgia Utility Contractor No.

This Bid is for: Mechanicsville & Jones Mill Road Water Main Replacement

November 12, 2026 **3:00 PM**

(Date) (Time)

1.02 The undersigned Bidder proposes and agrees, if this Bid is accepted, to enter into an Agreement with Owner in the form included in the Bidding Documents to perform all Work as specified or indicated in the Bidding Documents for the prices and within the times Indicated in this Bid and in accordance with the other terms and conditions of the Bidding Documents.

ARTICLE 2 – BIDDER'S ACKNOWLEDGMENTS

2.01 Bidder accepts all of the terms and conditions of the Instructions to Bidders, including without limitation those dealing with the disposition of Bid security. This Bid will remain subject to acceptance for 60 days after the Bid opening, or for such longer period of time that Bidder may agree to in writing upon request of Owner.

ARTICLE 3 – BIDDER'S REPRESENTATIONS

3.01 In submitting this Bid, Bidder represents that:

A. Bidder has examined and carefully studied the Bidding Documents, the other related data identified in the Bidding Documents, and the following Addenda, receipt of which is hereby acknowledged.

Addendum No.	Addendum Date
1	10/28/26
2	11/4/26

B. Bidder has visited the Site and become familiar with and is satisfied as to the general, local and Site conditions that may affect cost, progress, and performance of the Work.

C. Bidder is familiar with and is satisfied as to all federal, state and local laws and regulations that may affect cost, progress and performance of the Work.

D. Bidder has carefully studied all reports (if applicable) of explorations and tests of subsurface conditions at or contiguous to the Site and all drawings of physical conditions in or relating to existing surface or subsurface structures at or contiguous to the Site (except Underground Facilities) which have been identified and reports and drawings of Hazardous Environmental Conditions that have been identified in SC-4.06.

E. Bidder has obtained and carefully studied (or accepts the consequences for not doing so) all additional or supplementary examinations, investigations, explorations, tests, studies and data concerning conditions (surface, subsurface and Underground Facilities) at or contiguous to the Site which may affect cost, progress, or performance of the Work or which relate to any aspect of the means, methods, techniques, sequences, and procedures of construction to be employed by Bidder, including applying the specific means, methods, techniques, sequences, and procedures of construction expressly required by the Bidding Documents to be employed by Bidder, and safety precautions and programs incident thereto.

F. Bidder does not consider that any further examinations, investigations, explorations, tests, studies, or data are necessary for the determination of this Bid for performance of the Work at the price(s) bid and within the times and in accordance with the other terms and conditions of the Bidding Documents.

G. Bidder is aware of the general nature of work to be performed by Owner and others at the Site that relates to the Work as indicated in the Bidding Documents.

H. Bidder has correlated the information known to Bidder, information and observations obtained from visits to the Site, reports and drawings identified in the Bidding Documents, and all additional examinations, investigations, explorations, tests, studies, and data with the Bidding Documents.

I. Bidder has given Engineer written notice of all conflicts, errors, ambiguities, or discrepancies that Bidder has discovered in the Bidding Documents, and the written resolution thereof by Engineer is acceptable to Bidder.

J. The Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for the performance of the Work for which this Bid is submitted.

K. Bidder will submit written evidence of its authority to do business in the state where the Project is located not later than the date of its execution of the Agreement.

ARTICLE 4 – FURTHER REPRESENTATIONS

4.01 Bidder further represents that:

A. This Bid is genuine and not made in the interest of or on behalf of any undisclosed individual or entity and is not submitted in conformity with any agreement or rules of any group, association, organization or corporation;

B. Bidder has not directly or indirectly induced or solicited any other Bidder to submit a false or sham Bid;

C. Bidder has not solicited or induced any individual or entity to refrain from bidding; and

D. Bidder has not sought by collusion to obtain for itself any advantage over any other Bidder or over Owner.

ARTICLE 5 – BASIS OF BID

5.01 Bidder will complete the Work in accordance with the Contract Documents for the following price(s):

UNIT PRICE BID PROPOSAL

Mechanicsville & Jones Mill Road Water Main Replacement – Phase I

ITEM No.	DESCRIPTION	ESTIMATED QUANTITY	UNIT OF MEASURE	UNIT PRICE	TOTAL PRICE
WATER MAIN SYSTEM					
1.	8" PC 350 DIP Water Main (Includes all Rest. Jt. & Poly Wrap "Bagging")	4,346	LF		
2.	6" PC 350 DIP Water Main (Includes all Rest. Jt. & Poly Wrap "Bagging")	70	LF		
3.	2" Municipex SDR 9 Water Service	818	LF		
4.	8" x 8" Wet Tapping Sleeve with 8" Gate Valve	2	EA		
5.	6" x 6" Wet Tapping Sleeve with 6" Gate Valve	3	EA		
6.	2" Service Saddle with 2" Ball Valve	3	EA		
7.	8" Gate Valve	11	EA		
8.	2" Ball Valve	6	EA		
9.	Connect to Exist. 6" Water Main	4	EA		
10.	Connect to Exist. 2" Water Main	3	EA		
11.	Water Air Release Valve Assy.	3	EA		
12.	Fire Hydrant Assembly	7	EA		
13.	Abandon Exist. Water Main - In Place (7 WM's 1.5" to 6")	1	LS		
14.	3/4" Residential Service Meter Box Assembly (Short Side Single)	33	EA		
15.	3/4" Residential Service Meter Box Assembly (Long Side Single)	26	EA		
16.	Remove and Replace Exist. Water Meter Settings	14	EA		
17.	Relocate Exist. Meter to Exist. R/W	8	EA		

UNIT PRICE BID PROPOSAL
Mechanicsville & Jones Mill Road Water Main Replacement – Phase I

ITEM No.	DESCRIPTION	ESTIMATED QUANTITY	UNIT OF MEASURE	UNIT PRICE	TOTAL PRICE
18.	Cast Iron Specials	3.3	TN		
19.	Uncased Bore (all sizes)	375	LF		
20.	Sterilization & Pressure Testing	5,234	LF		
MISCELLANEOUS					
21.	Stabilization Stone	80.0	TN		
22.	Trench Rock Blasting/Breaker and Excavation	180	CY		
23.	Remove & Replace Asphalt or Concrete Pavement (For Service City Request)	130	LF		
24.	Remove & Replace Asphalt or Concrete Pavement	279	SY		
25.	Remove & Replace Gravel Driveway	58	LF		
26.	Remove & Replace Concrete Driveway	174	SY		
27.	Remove & Replace Asphalt Driveway	25	SY		
28.	Remove & Replace Concrete Sidewalk	26	LF		
29.	Remove & Replace 24" x 6" Concrete Curb & Gutter	20	LF		
30.	Remove & Replace Exist. Driveway Culvert Pipe	22	LF		
31.	Mill Asphalt Pavement 1.5" Depth	2,286	SY		
32.	1.5" Recycled Asphalt Concrete 12.5 mm Superpave, Level B (165 lb/sy)	189	TN		
33.	Mulching, Temporary & Permanent Grassing (Ds1, Ds2 & Ds3)	4,075	LF		
34.	Sodding (Ds4)	200	LF		
35.	Silt Fence Type "NS" Non-Sensitive (Sd1-NS)	2,510	LF		
36.	Inlet Sediment Trap (Sd2)	4	EA		
37.	Check Dam (Cd-S)	2	EA		
38.	Check Dam (Cd-Hb)	15	EA		
39.	Slope Stabilization (Ss)	5,000	SY		
40.	Storm Water Sampler for NPDES, Automatic or Manual	1	LS		
41.	Monitoring, NOI, NOT, Record Keeping & Reporting NPDES to GA EPD	1	LS		
42.	Materials Testing	1	LS	$5,000.00	$5,000.00
43.	Cash Allowance (Authorized by Owner & Engineer)	1	LS	$75,000.00	$75,000.00

SUB-TOTAL AMOUNT PHASE I BID _____
(In Figures)

_____
(In Words)

UNIT PRICE BID PROPOSAL
Mechanicsville & Jones Mill Road Water Main Replacement – Phase II

ITEM No.	DESCRIPTION	ESTIMATED QUANTITY	UNIT OF MEASURE	UNIT PRICE	TOTAL PRICE
WATER MAIN SYSTEM					
1.	8" PC 350 DIP Water Main (Includes all Rest. Jt. & Poly Wrap "Bagging")	6,785	LF		
2.	2" Municipex SDR 9 Water Service	1,069	LF		
3.	8" x 8" Wet Tapping Sleeve with 8" Gate Valve	3	EA		
4.	6" x 6" Wet Tapping Sleeve with 6" Gate Valve	1	EA		
5.	2" Service Saddle with 2" Ball Valve	2	EA		
6.	8" Gate Valve	18	EA		

ITEM No.	DESCRIPTION	ESTIMATED QUANTITY	UNIT OF MEASURE	UNIT PRICE	TOTAL PRICE
7.	6" Gate Valve	1	EA		
8.	2" Ball Valve	4	EA		
9.	Connect to Exist. 6" Water Main	1	EA		
10.	Connect to Exist. 8" Water Main	2	EA		
11.	Water Air Release Valve Assy.	1	EA		
12.	Fire Hydrant Assembly	11	EA		
13.	Abandon Exist. Water Main - In Place (11 WM's 1.5" to 6")	1	LS		
14.	3/4" Residential Service Meter Box Assembly (Short Side Single)	43	EA		
15.	3/4" Residential Service Meter Box Assembly (Long Side Single)	34	EA		
16.	3/4" Residential Service Meter Box Assembly (Long Side Double)	1	EA		
17.	Remove and Replace Exist. Water Meter Settings	22	EA		
18.	Relocate Exist. Meter to Exist. R/W	7	EA		
19.	Cast Iron Specials	6.3	TN		
20.	Uncased Bore (all sizes)	450	LF		
21.	Sterilization & Pressure Testing	7,854	LF		
MISCELLANEOUS					
22.	Stabilization Stone	130.0	TN		
23.	Trench Rock Blasting/Breaker and Excavation	305	CY		
24.	Remove & Replace Asphalt or Concrete Pavement (For Service City Request)	280	LF		
25.	Remove & Replace Asphalt or Concrete Pavement	330	SY		
26.	Remove & Replace Gravel Driveway	435	LF		
27.	Remove & Replace Concrete Driveway	16	SY		
28.	Remove & Replace Asphalt Driveway	25	SY		
29.	Remove & Replace Concrete Sidewalk	46	LF		
30.	Remove & Replace 24" x 6" Concrete Curb & Gutter	20	LF		
31.	Remove & Replace Exist. Driveway Culvert Pipe	22	LF		
32.	Mill Asphalt Pavement 1.5" Depth	3,793	SY		
33.	1.5" Recycled Asphalt Concrete 12.5 mm Superpave, Level B (165 lb/sy)	313	TN		
34.	Tree Removal (as shown on the plans)	1	LS		
35.	Mulching, Temporary & Permanent Grassing (Ds1, Ds2 & Ds3)	5,158	LF		
36.	Sodding (Ds4)	200	LF		
37.	Silt Fence Type "NS" Non-Sensitive (Sd1-NS)	4,536	LF		
38.	Inlet Sediment Trap (Sd2)	1	EA		
39.	Check Dam (Cd-Hb)	17	EA		
40.	Slope Stabilization (Ss)	5,000	SY		
41.	Storm Water Sampler for NPDES, Automatic or Manual	1	LS		
42.	Monitoring, NOI, NOT, Record Keeping & Reporting NPDES to GA EPD	1	LS		
43.	Materials Testing	1	LS	$5,000.00	$5,000.00
44.	Cash Allowance (Authorized by Owner & Engineer)	1	LS	$75,000.00	$75,000.00

SUB-TOTAL AMOUNT PHASE II BID _____

(In Figures)

_____

(In Words)

TOTAL AMOUNT BASE BID (PH. I & PH. II) _____

(In Figures)

_____

(In Words)

ARTICLE 6 – TIME OF COMPLETION

6.01 Bidder agrees that the Work will be Substantially Complete in accordance with Paragraph 14.04 of the General Conditions, and will be Final Complete and ready for final payment in accordance with Paragraph 14.07 of the General Conditions on or before the date indicated in the Agreement.

6.02 Bidder accepts the provisions of the Agreement as to liquidated damages in the event of failure to complete the Work within the Contract Time.

6.03 **Phase I shall be Substantially Complete within 180 calendar days, and Final Completion within 210 calendar days from the date of notice to proceed of the contract. Phase II shall be Substantially Complete within 180 calendar days, and Final Completion within 210 calendar days from Phase I Substantially Complete date. Contractor will not be allowed to start Phase II until Phase I is Substantially Complete.**

ARTICLE 7 – ATTACHMENTS TO THIS BID

7.01 The following documents are attached to and made a condition of this Bid:

A. Bid Bond – Section 00430.

B. Form of Qualification of Bidder – Section 00450.

C. Affidavit of Non-Collusion – Section 00480.

D. Immigration and Security Form – Section 00490.

ARTICLE 8 – DEFINED TERMS

8.01 The terms used in this Bid with initial capital letters have the meanings stated in the Instructions to Bidders, the General Conditions, and the Supplementary Conditions.

ARTICLE 9 – BID SUBMITTAL

9.01 This Bid submitted by:

If Bidder is:

<u>An Individual</u>

Name (typed or printed): _____

By: _____
(Individual's signature)

A Partnership

Partnership Name (typed or printed):_____

By: _____
(Signature of general partner -- attach evidence of authority to sign)

Name (typed or printed): _____

A Corporation

Corporation Name: _____

State of Incorporation: _____

By: _____
(Signature -- attach evidence of authority to sign)

Name (typed or printed): _____

Title: _____
(CORPORATE SEAL)

Attest _____

Date of Authorization to do business in the state of Georgia is ___/___/___

END OF SECTION