November 5, 2026

TO: **All Potential Bidders**

SUBJECT: **Intersection Improvements**

Bid Ref. **#27-024**

Bid Opening Date & Time: **November 10, 2026 @ 2:30 p.m.**

ADDENDUM NO. 2

The items contained in this addendum are added to and/or deleted from and become part of the Bid Documents, Project Manual, Drawings and other proposal documents for the above-referenced Invitation to Bid. Bidders **must acknowledge receipt** of the Addendum on the Bid Form and also on the Addendum Acknowledgement Form, which is a required Appendix to the Bid Form, when the bids are submitted.

QUESTIONS AND ANSWERS

1. Will the vendor be responsible for providing tree removal and trimming services? ***Answer: Yes, the vendor is responsible for all required tree removal and trimming services. Bidders must coordinate directly with Public Works contact John Bland via email at JBland@albanyga.gov to facilitate and manage all necessary removals.***

2. Will the vendor be responsible for removing abandoned fiber cables in relation to the replacement of the mast arms? ***Answer: Yes, the contractor is responsible for the safe removal and disposal of all abandoned fiber cables encountered during the mast arm replacement work.***

3. What type of camera does the City want? The mount can be pole mounted or J-pipe on a luminaire. Is it a fixed or PTZ camera? ***Answer:***

Component	Requirement
• **Camera types**	**Type 1: PTZ dome**
• Image quality	1080p resolution; configurable frame rate from 5–30 fps
• **PTZ zoom**	**Prefer 40x but Minimum 30× optical and 2× digital**

Component	Requirement
• Viewing	Day/night operation, defog, wide dynamic range, electronic image stabilization
• PTZ operation	Continuous 360° pan; at least 64 presets and eight tours
• Streaming	At least three simultaneous video streams
• Management	Browser access, password-controlled accounts, remote reboot and firmware updates
• Power recovery	Retains configuration and resumes operation without manual adjustment

ATTACHMENTS

1. 27-024_Bid_Form_Updated (linked)
2. 27-024_City of Albany Intersection Design – Site 1-8_Updated (linked)
3. 27-024_Specifications_Manual_Updated (linked)
4. 27-024_City of Albany Intersection Design - 8th Ave and Palmyra_Updated (linked)

https://www.dropbox.com/scl/fo/ioeadoz8fghfgtpztpbw2/AB9r0Td3dQNybtja04NIssc?rlkey=kt0br1dixmmnxp1f0t0eskyve&st=mzjy29a7&dl=0

End of Addendum 2

Ricky Gladney

Ricky Gladney, Buyer

CC: Joseph Threadcraft, Threadcraft Engineering
Ken Breedlove, Traffic Engineering Manager
All Design Team Project Engineers
All Known Bidders