BRUNSWICK-GLYNN COUNTY JOINT WATER & SEWER COMMISSION

October 14, 2026

PROJECT: **REQUEST FOR PROPOSAL NO. 27-006 CONSTRUCTION SERVICES FOR BASIN 4001 AND 4013 CIPP**

ADDENDUM: **ONE (1)**

DUE DATE: **TUESDAY, NOVEMBER 10, 2026 – 12:00PM, NOON**

THIS ADDENDUM IS FOR THE PURPOSE OF ANSWERING THE FOLLOWING QUESTIONS:

1) **QUESTION: Is JWSC accepting UV heat cure/UV CIPP as an approved equal or alternative for this project?**

   ANSWER: JWSC strongly prefers water cure on CIPP. UV curing may be used after pre-CCTV and with written approval by Owner (JWSC) depending on active infiltration into the lines.

2) **QUESTION: In review of this project, it was noticed that the bid includes approximately 27,000 LF of mainline CIPP and 408 service connection reinstatements. Would JWSC incorporate lateral lining into its sewer rehabilitation program?**

   ANSWER: At this time, lateral lining is cost prohibitive to the project, but could be a future option.

3) **QUESTION: Would spiral-wound PVC lining (Sekisui) be accepted in place of the CIPP lining for this project or is it strictly CIPP only?**

   ANSWER: Due to the size and scope of this project, JWSC prefers the lining be CIPP only.

4) QUESTION: Can the JWSC please confirm whether there are any DBE requirements or Good Faith Effort (GFE) requirements associated with this project? If so, please advise what documentation, if any, is required to be submitted at the time of bid and/or following bid award. Additionally, please confirm whether any DBE forms or utilization documents must be included with the bid package.

ANSWER: No, the JWSC is not using any funding sources for this project that have DBE or Good Faith Effort requirements.

All applicants under this Request for Proposal are kindly requested to acknowledge receipt of this Addendum in original only.

ACKNOWLEDGEMENT
ADDENDUM: ONE (1)

DATE:_____

The above Addendum is hereby acknowledged:

_____

(NAME OF BIDDER)

_____ _____

Signature **Title**