LEE COUNTY

Life works well here.

Invitation to Bid
2026 SAP Road Striping Project
ITB# 120326

The Lee County Board of Commissioners is accepting sealed written bids from qualified contractors for road striping services for the following 25 roads in Lee County: Smithville Road from Leesburg City Limits to S.R. 118, Pinewood Road from S.R. 32 to U.S. 19, New York Road from Lee County Line to S.R. 195, Philema Road from New York Road to S.R. 32, Old Stage Road from S.R. 32 to end of pavement, Graves Spring Road from S.R. 32 to Forrester Parkway, Garrett Road from Graves Spring Road to Philema Road, White Pond Road from Philema Road to Hattie Bell Road, Thundering Springs Road from Philema Road to White Pond Road, Miller Road from White Pond Road to Stocks Dairy Road, Flowing Well Road from White Pond Road to Stocks Dairy Road, Lovers Lane Road from S.R. 32 to Dougherty County Line, Mayhaw Road from U.S. 19 to Lovers Lane Road, Armena Road from S.R. 32 to U.S. 82, Palmyra Road from S.R. 32 to Fussell Road, James Pond Road from S.R. 32 to Palmyra Road, Oakland Road from U.S. 82 to Palmyra Road, Kinchafoonee Creek Road from Creekside Drive to U.S. 19, Haley Drive from S.R. 133 to Lovers Lane Road, Marlow Lane from West Doublegate Drive to U.S. 82, N Doublegate Drive from U.S. 82 to the Dougherty county Line, Winnifred Road from Cookville Road to U.S. 82, Hugh Road from Ledo Road to Fussell Road, Capstone Connector from Ledo Road to Fussell Road, and Century Road from Palmyra Road to U.S. 19. In general, these roads are to be restriped with either high build or thermoplastic paint as called for in the Bid Form. Striping is to match the existing striping unless otherwise noted on the bid form. Other included items are traffic control, rumble strips, stop bars, and other misc. items pertaining to the project. See attached Bid Form for detailed quantities. Maps (see Exhibit A), specifications, bid form, and other information are attached.

If you choose to submit a written bid on this project, your sealed bid must be marked **"2026 SAP Road Striping Project"** and delivered to the Lee County Board of Commissioners Office at the T. Page Tharp Building located at 102 Starksville Avenue North Leesburg, Georgia 31763, **no later than 10:00 am on Thursday, December 3, 2026**. All bids will be opened and read aloud during a **public bid opening at 10:00 am on Thursday, December 3, 2026**, in the Opal Cannon Auditorium of the T. Page Tharp Building located at 102 Starksville Avenue North Leesburg, Georgia 31763. The public is invited to attend this bid opening. No bids shall be withdrawn for a period of 60 days after the bid opening.

Bidders are required to examine all maps, specifications and data mentioned in the specifications, contracts, or proposals on file with Lee County at 102 Starksville Avenue North Leesburg, Georgia, or at such other location or locations established by Lee County from time to time with respect to such proposed project. No plea of ignorance of conditions that exist or that may exist after the date of these instructions, or of any conditions or difficulties that may be encountered in the execution of the work under any contract issued hereunder, resulting from the bidder's failure to make the necessary examinations and investigations, shall be accepted as an excuse for any failure or omission on the part of the successful bidder to fulfill in every detail all requirements of any contract issued hereunder. Nor will such reasons be accepted as a basis for any claims whatsoever for extra compensation, change orders, or an extension of time to complete the required work under the contract issued hereunder.

Any bid submitted unsealed, unsigned, fax transmissions, email transmissions, or received subsequent to the aforementioned date and time, will be disqualified. Contractors are responsible for informing any commercial delivery service, if used, of all delivery requirements and for ensuring that the required address information appears on the outer wrapper or envelope used by such service. The submittal must be signed by a company officer who is legally authorized to enter into a contractual relationship in the name of the contractor. Failure to comply with the written requirements for this project may result in disqualification of the submittal by the Lee County Board of Commissioners.

The Board of Commissioners reserves the right to accept or reject any or all bids received and/or disregard informalities or irregularities in the Bids received. **There will be no addendums to the contract once the contract has been accepted and signed, unless initiated by the County.** If additional information is needed, please contact **Brent Davis, Project Manager, Reliable Engineering at (229) 224-3299 or brent@reliableeng.net.** The Lee County Board of Commissioners is an Equal Opportunity Employer.

In the event that any corrections or amendments to this Invitation to Bid are deemed necessary or appropriate, such corrections or amendments shall be issued by the Lee County Board of Commissioners in written addenda issued prior to the due date for bids. Potential Bidders should not rely on any representations, statements or explanations other than those made in this document or in any addenda to this document. Where there appears to be a conflict between this Invitation to Bid and any addenda issued, the last addenda issued will prevail. Addenda will be published on the Lee County Board of Commissioners' website at www.leecountyga.gov. Potential Bidders are encouraged to check such website regularly for immediate access to issued addenda.

All expenses involved with the preparation and submission of the Invitation to Bid to the Lee County Board of Commissioners, or any work performed in connection therewith is the responsibility of the Bidder(s). Submission of any proposal indicates acceptance of the conditions contained in this document unless clearly and specifically noted otherwise in the proposal.

The Lee County Board of Commissioners operates with a five (5) member County Commission. It is anticipated that Bidder(s) may need to make one or more appearances at County Commission meetings to answer questions or present results. The documentation provided herein is intended to provide a common methodology of development and basic technical skills for proposal purposes.

Your written and sealed bid must include at a minimum:

- ❑ Completed attached bid form and bid schedule with a total cost of services
- ❑ A bid bond, or an irrevocable letter of credit, or a cashier's check in the amount of 10% of the bid amount payable to the Lee County Board of Commissioners from a company authorized to do business in the State of Georgia
- ❑ An authorized signature on written oath stating that the contractor has not restricted competitive bidding

In addition, the successful contractor shall submit the following items within ten calendar days of written notification from the county of the bid award:

- ❑ Proof of workers' compensation insurance if required by Georgia law
- ❑ Proof of general liability insurance in the amount of at least $1,000,000.00 naming the Lee County Board of Commissioners as an additional insured
- ❑ Proof of automobile liability insurance in the amount of at least $1,000,000.00 naming the Lee County Board of Commissioners as an additional insured
- ❑ A performance bond in the amount of the bid. The performance bond shall be payable to the Lee County Board of Commissioners from a company authorized to do business in the State of Georgia.
- ❑ A payment bond in the amount of the bid. The payment bond shall be payable to the Lee County Board of Commissioners from a company authorized to do business in the State of Georgia.
- ❑ Written certification that the contractor operates a drug free workplace in accordance with O.C.G.A 50-24-1 through 50-24-6
- ❑ Completed SAVE Affidavit
- ❑ Completed Contractor's Affidavit
- ❑ Completed Subcontractor's Affidavit, if applicable
- ❑ Signed contract (prepared by the County)

Project Information

The Contractor Shall:

1) Verify the quantities of materials needed.

2) Begin work on this project within 90 calendar days of written notification from the County to proceed.

3) Perform all work on this project in accordance with the Georgia Department of Transportation Standard Specifications, 2013 Edition, as amended by supplemental specifications and contract provisions.

4) Maintain all aspects of the project including access to homes and traffic control devices until the Board of Commissioners accepts the project.

5) Use only attached bid form and items list.

6) Complete all work on this project by 5:00pm 90 days from the time the notice to proceed is received, or liquidated damages of $100.00 per day will be assessed against the contractor. An extension of time may be granted by **Lee County, in its sole and absolute discretion, beyond the deadline for project completion, in the event that, during the course of the performance of the contract, the work required by the contract cannot be performed as a direct result of inclement weather. No liquidated damages will be charged or payable with respect to any day that Lee County determines that the contract work cannot be performed due to inclement weather, and the date for completion shall be extended day for day for each day that it is determined that the contractor is unable to perform due to inclement weather.**

The County Shall:

1) Clip back shoulders prior to edge line striping.

2) Pay the contractor in monthly payments in accordance with voucher reports. A ***ten percent retainage*** of the bid amount will be withheld from the contractor until the Board of Commissioners accepts the project. This contract shall not exceed the contractor's bid amount without prior written approval from the Board of Commissioners. All extra work approved by the Board of Commissioners shall be paid on the basis of unit price as stated in the contractor's bid.

SPECIAL PROVISION

1) Contractors must be Georgia Department of Transportation certified.

2) STANDARD SPECIFICATIONS. Construction shall conform to Georgia Department of Transportation Standard Specifications, latest edition.

3) TRAFFIC. The contractor shall maintain safe traffic conditions at all times.

4) All bids must have an affidavit from the contractor and any subcontractors that it has registered with a federal work authorization program, for example E-Verify, operated by U.S. Department of Homeland Security to verify immigration status of employee (O.C.G.A. 13-10-91).

5) STRIPING. Striping on indicated road may include, but not be limited to centerline, edge, stop bars, hatching, and R.P.M.'s. **All existing striping should be noted and replicated after resurfacing.** Temporary striping shall include center and edge lines on all roads that currently have striping. Final centerline and edge lines shall be high build paint per GDOT Section 652 or thermoplastic per Section 653. Stop bars and rumble strips shall be Thermoplastic per Section 653, and R.P.M.'s per Section 654. All striping shall conform to the MUTCD (latest edition).

6) INSURANCE REQUIREMENTS

A) The Contractor shall carry Public Liability, Property Damage, and Vehicle Liability Insurance covering operation on and off site, with the Lee County Board of Commissioners named as an additional insured, in the limits of:

1. Public Liability	$1,000,000.00
2. Property Damage	$1,000,000.00
3. Automobile Liability	B.I. $1,000,000.00
	P.D. $1,000,000.00

B) The Contractor shall carry Workers' Compensation Insurance for all employees engaged in the work, and shall require all Sub-Contractors to do so.

C) The Contractor shall be solely responsible for all liabilities, suits, actions, and claims of every character whatsoever incurred or brought for or on account of any injuries (**including death**) damages, or loss incurred, received, or sustained or claimed to have been incurred, received or sustained by any person or persons or to any property, real or personal, whether on or adjacent to the job site or not, rising out of or in any way connected with the matters and things set forth in these specifications, or other of the contract documents, whether due to the negligence of Contractor, Lee County, or otherwise, and the Contractor covenants and agrees to indemnify and save harmless **Lee County, and its elected officials, employees, and** from **any and all** from all liabilities charges, expenses and cost on account of or by reason of any such injuries, damages, liabilities, claims, suits, or losses, **referenced above**, however occurring, including any costs incurred in defending against the same. To further assure the performance of this covenant the Contractor shall procure and constantly maintain in force at its expense, the liability insurance set forth in Section 1B – 16, "Requirement of Contract Surety."

7) A minimum of a 3-day notice shall be given to the owner, in writing, prior to any full road closures.

8) Work and payment for items specifically not listed on the bid schedule will be considered incidental to the pay items in which the work is required to be performed.

Invitation to Bid
Road Resurfacing Services
RFP# 120326

Bid Form

Name of Bidder/ Vendor: _____

Contact Person: _____

Mailing Address: _____

_____

Telephone: _____

Email: _____

It is agreed by the undersigned bidder that the signature and submission of this bid represents the bidder's acceptance of all terms, conditions, and requirements of the bid specifications and, if awarded, the bid will represent the agreement between the parties. No addendums will be allowed unless initiated by the County.

SMITHVILLE ROAD (10.41 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
1	Thermo Solid White Striping, Fog Lines	20.82	LM		
2	Thermo Yellow Striping, Centerline Replaced In-Kind	10.41	LM		
3	Raised Pavement Markers (RPM's)	10.41	LM		
4	Yellow Hatching	1	LS		
5	White Hatching	1	LS		
6	Thermo Rumble Strips (Set of Three)	1	EA		
7	Stop Bar (Thermo)	2	EA		
				Sub Total	

PINEWOOD ROAD (5.92 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
8	Thermo Solid White Striping, Fog Lines	11.84	LM		
9	Thermo Yellow Striping, Centerline Replaced In-Kind	5.92	LM		
10	Raised Pavement Markers (RPM's)	5.92	LM		
11	Thermo Rumble Strips (Set of Three)	1	EA		
12	Turn Arrow	1	EA		
				Sub Total	

NEW YORK ROAD (15.78 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
13	Thermo Solid White Striping, Fog Lines	31.56	LM		
14	Thermo Yellow Striping, Centerline Replaced In-Kind	15.78	LM		
15	Raised Pavement Markers (RPM's)	15.78	LM		
16	Stop Bar (Thermo)	1	EA		
				Sub Total	

PHILEMA ROAD (4.70 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
17	Thermo Solid White Striping, Fog Lines	9.40	LM		
18	Thermo Yellow Striping, Centerline Replaced In-Kind	4.7	LM		
19	Raised Pavement Markers (RPM's)	4.7	EA		
20	Thermo Rumble Strips (Set of Three)	1	EA		
21	Stop Bar (Thermo)	1	EA		
				Sub Total	

OLD STAGE ROAD (1.22 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
22	High Build Solid White Striping, Fog Lines	2.44	LM		
23	High Build Yellow Centerline Striping, In-Kind	1.22	LM		
24	Raised Pavement Markers (RPM's)	1.22	EA		
25	Stop Bar (Thermo)	3	EA		
				Sub Total	

GRAVES SPRING ROAD (5.19 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
26	Thermo Solid White Striping, Fog Lines	10.38	LM		
27	Thermo Yellow Striping, Centerline Replaced In-Kind	5.19	LM		
28	Raised Pavement Markers (RPM's)	5.19	EA		
29	Thermo Rumble Strips (Set of Three)	1	EA		
				Sub Total	

GARRETT ROAD (1.02 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
30	High Build Solid White Striping, Fog Lines	2.04	LM		
31	High Build Yellow Centerline Striping, In-Kind	1.02	LM		
32	Raised Pavement Markers (RPM's)	1.02	LM		
33	Stop Bar (Thermo)	1	EA		
				Sub Total	

WHITE POND ROAD (3.46 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
34	High Build Solid White Striping, Fog Lines	6.92	LM		
35	High Build Yellow Centerline Striping, In-Kind	3.46	LM		
36	Raised Pavement Markers (RPM's)	3.46	EA		
37	Stop Bar (Thermo)	2	EA		
				Sub Total	

THUNDERING SPRINGS ROAD (0.41 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
38	High Build Solid White Striping, Fog Lines	0.82	LM		
39	High Build Yellow Centerline Striping, In-Kind	0.41	LM		
40	Raised Pavement Markers (RPM's)	0.41	EA		
41	Stop Bar (Thermo)	1	EA		
				Sub Total	

MILLER ROAD (2.10 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
42	High Build Solid White Striping, Fog Lines	4.20	LM		
43	High Build Yellow Centerline Striping, In-Kind	2.1	LM		
44	Raised Pavement Markers (RPM's)	2.1	EA		
45	Stop Bar (Thermo)	1	EA		
				Sub Total	

FLOWING WELL ROAD (1.00 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
46	High Build Solid White Striping, Fog Lines	2.00	LM		
47	High Build Yellow Centerline Striping, In-Kind	1.00	LM		
48	Raised Pavement Markers (RPM's)	1.00	EA		
49	Stop Bar (Thermo)	2	EA		
				Sub Total	

LOVERS LANE ROAD (7.62 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
50	Thermo Solid White Striping, Fog Lines	15.24	LM		
51	Thermo Yellow Centerline Striping, In-Kind	7.62	LM		
52	Raised Pavement Markers (RPM's)	7.62	LM		
53	Yellow Hatching	1	LS		
54	White Hatching	1	LS		
55	Turn Arrow (Thermo)	18	EA		
56	Stop Bar (Thermo)	2	EA		
				Sub Total	

MAYHAW ROAD (1.71 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
57	High Build Solid White Striping, Fog Lines	3.42	LM		
58	High Build Yellow Centerline Striping, In-Kind	1.71	LM		
59	Raised Pavement Markers (RPM's)	1.71	EA		
60	RR Crossing (Thermo)	1	EA		
61	Stop Bar (Thermo)	3	EA		
				Sub Total	

ARMENA ROAD (4.93 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
62	Thermo Solid White Striping, Fog Lines	9.86	LM		
63	Thermo Yellow Centerline Striping, In-Kind	4.93	LM		
64	Raised Pavement Markers (RPM's)	4.93	EA		
65	Thermo Rumble Strips (Set of Three)	1	EA		
66	Stop Bar (Thermo)	2	EA		
				Sub Total	

PALMYRA ROAD (6.57 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
67	Thermo Solid White Striping, Fog Lines	13.14	LM		
68	Thermo Yellow Centerline Striping, In-Kind	6.57	LM		
69	Raised Pavement Markers (RPM's)	6.57	EA		
70	Stop Bar (Thermo)	3	EA		
				Sub Total	

JAMES POND ROAD (1.32 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
71	Thermo Solid White Striping, Fog Lines	2.64	LM		
72	Thermo Yellow Centerline Striping, In-Kind	1.32	LM		
73	Raised Pavement Markers (RPM's)	1.32	LM		
74	Thermo Rumble Strips (Set of Three)	1	EA		
				Sub Total	

OAKLAND ROAD (4.42 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
75	Thermo Solid White Striping, Fog Lines	8.84	LM		
76	Thermo Yellow Centerline Striping, In-Kind	4.42	LM		
77	Raised Pavement Markers (RPM's)	4.42	EA		
78	Thermo Rumble Strips (Set of Three)	2	EA		
79	Stop Bar (Thermo)	1	EA		
				Sub Total	

KINCHAFOONEE CREEK ROAD (0.98 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
80	Thermo Solid White Striping, Fog Lines	1.96	LM		
81	Thermo Yellow Centerline Striping, In-Kind	0.98	LM		
82	Raised Pavement Markers (RPM's)	0.98	EA		
83	Turn Arrows (Thermo)	2	EA		
84	Stop Bar (Thermo)	1	EA		
				Sub Total	

HALEY DRIVE (1.48 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
85	Thermo Solid White Striping, Fog Lines	2.96	LM		
86	Thermo Yellow Centerline Striping, In-Kind	1.48	LM		
87	Raised Pavement Markers (RPM's)	1.48	EA		
88	Stop Bar (Thermo)	1	EA		
				Sub Total	

MARLOW LANE (1.33 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
89	High Build Solid White Striping, Fog Lines	2.66	LM		
90	High Build Yellow Centerline Striping, In-Kind	1.33	LM		
91	Raised Pavement Markers (RPM's)	1.33	LM		
92	Turn Arrows (Thermo)	7	EA		
93	Stop Bar (Thermo)	14	EA		
				Sub Total	

NORTH DOUBLEGATE DRIVE (1.08 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
94	High Build Solid White Striping, Fog Lines	2.16	LM		
95	High Build Yellow Centerline Striping, In-Kind	1.08	LM		
96	Raised Pavement Markers (RPM's)	1.08	EA		
97	Turn Arrows (Thermo)	7	EA		
98	Stop Bar (Thermo)	14	EA		
				Sub Total	

WINNIFRED ROAD (0.61 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
99	High Build Solid White Striping, Fog Lines	1.22	LM		
100	High Build Yellow Centerline Striping, In-Kind	0.61	LM		
101	Raised Pavement Markers (RPM's)	0.61	EA		
102	Stop Bar (Thermo)	2	EA		
				Sub Total	

HUGH ROAD (0.41 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
103	Thermo Solid White Striping, Fog Lines	0.82	LM		
104	Thermo White Dashed Line	0.82	LM		
105	Thermo Yellow Centerline Striping, In-Kind	0.41	LM		
106	Raised Pavement Markers (RPM's)	0.41	LM		
107	Turn Arrows (Thermo)	12	EA		
				Sub Total	

CAPSTONE CONNECTOR (0.76 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
108	Thermo Solid White Striping, Fog Lines	1.52	LM		
109	Thermo Yellow Centerline Striping, In-Kind	0.76	LM		
110	Raised Pavement Markers (RPM's)	0.76	EA		
				Sub Total	

CENTURY ROAD WEST (1.92 MILES)

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
111	High Build Solid White Striping, Fog Lines	3.84	LM		
112	High Build Yellow Centerline Striping, In-Kind	1.92	LM		
113	Raised Pavement Markers (RPM's)	1.92	EA		
114	Stop Bar (Thermo)	1	EA		
				Sub Total	

TOTAL FOR ALL ROADS _____

Authorized Signature: _____ **Title:** _____

Name Printed: _____ **Date:** _____

MEASUREMENT AND PAYMENT SECTION

Description: **Traffic Control**
Payment: None
Measurement: None
Work Required: To be included in line item for which it pertains. Includes providing, placing, moving, operating, and maintaining the necessary barricades, signs, and devices for the life of Project, and removing barricades, signs, and devices when the Work is complete. No separate payment will be made for traffic control.

Description: **Solid High Build White Striping, Fog Lines**
Payment: Per Linear Mile
Measurement: Actual length of road down the edge of pavement for a single lane
Work Required: All labor, equipment, materials, tools, and incidental items necessary to complete the work for permanent high build white striping along both sides of the pavement, or outer lane, and complete job as specified in Section 652 – Painting Traffic Stripe in the GDOT Standard Specifications

Description: **High Build Yellow Centerline Striping, In-Kind**
Payment: Per Linear Mile
Measurement: Actual length of road down the centerline
Work Required: All labor, equipment, materials, tools, and incidental items necessary to complete the work for placing permanent high build yellow striping along the centerline of the pavement, replaced in-kind, and a complete job as specified in Section 652 – Painting Traffic Stripe in the GDOT Standard Specifications.

Description: **Solid Thermo White Striping, Fog Lines**
Payment: Per Linear Mile
Measurement: Actual length of road down the edge of pavement for a single lane
Work Required: All labor, equipment, materials, tools, and incidental items necessary to complete the work for permanent high build white striping along both sides of the pavement, or outer lane, and complete job as specified in Section 653 – Thermoplastic Traffic Stripe in the GDOT Standard Specifications

Description: **Thermo Yellow Centerline Striping, In-Kind**
Payment: Per Linear Mile
Measurement: Actual length of road down the centerline
Work Required: All labor, equipment, materials, tools, and incidental items necessary to complete the work for placing permanent high build yellow striping along the centerline of the pavement, replaced in-kind, and a complete job as specified in Section 653 – Thermoplastic Traffic Stripe in the GDOT Standard Specifications.

Description: **Stop Bars**
Payment: Each
Measurement: Each Stop Bar Placed
Work Required: All labor, equipment, materials, tools, and incidental items necessary to complete the work for replacing stop bars with thermoplastic paint as specified in Section 653 – Thermoplastic Traffic Stripe in the GDOT Standard Specifications.

Description: **Transverse Rumble Strips**
Payment: Each (Set of Three)
Measurement: Each Set of Rumble Strips Placed
Work Required: All labor, equipment, materials, tools, and incidental items necessary to complete the work for replacing stop bars with thermoplastic paint as specified in Section 653 – Thermoplastic Traffic Stripe in the GDOT Standard Specifications.

Description: **Turn Arrow**
Payment: Each
Measurement: Each Turn Arrow Placed
Work Required: All labor, equipment, materials, tools, and incidental items necessary to complete the work for replacing stop bars with thermoplastic paint as specified in Section 653 – Thermoplastic Traffic Stripe in the GDOT Standard Specifications.

Description: **Raised Pavement Markers**
Payment: Per Linear Mile
Measurement: Actual length of road down the centerline
Work Required: All labor, equipment, materials, tools, and incidental items necessary to complete the work for permanent raised pavement markers as specified in Section 654 – Raised Pavement Markers in the GDOT Standard Specifications. Raised Pavement Markers will follow GDOT Construction Details T-15A and T-15C.

Lee County, Georgia

Non-Collusion Certification

The undersigned bidder certifies that I have not directly or indirectly entered into any agreement, participated in any collusion, nor otherwise taken any action in restraint of free competitive bidding in connection with this submitted bid.

Authorized Signature: _____

Name Printed: _____

Name of Company: _____

Date: _____