CHEROKEE COUNTY BOARD OF COMMISSIONERS
Purchasing Department
1130 Bluffs Pkwy, Canton, GA 30114
Ph: 678-493-6000 | Fax: 678-493-6035

ADDENDUM # 1

Solicitation Number:	2026-031
Solicitation Name:	State Route 140 at CR309 Univeter Road Intersection Improvement Project 0017804 - Cherokee County
Addendum Release Date:	October 21, 2026

Prime Bidders/Proposers acknowledge the receipt of this Addendum by inserting the number and date in the appropriate position on the Proposal Form. Failure to do so may subject the Bidder/Proposer to disqualification. This Addendum is a part of the Contract Documents. It modifies them as follows:

Attachments as part of this Addendum:

- Pricing Form 10.21.2026

- Updated drawings:
  - 0017804_Amendment1
  - 0017804_Amendment1_01-0001
  - 0017804_Amendment1_03-0001
  - 0017804_Amendment1_05-0009
  - 0017804_Amendment1_05-0011
  - 0017804_Amendment1_05-0012
  - 0017804_Amendment1_05-0014
  - 0017804_Amendment1_06-0001
  - 0017804_Amendment1_06-0005
  - 0017804_Amendment1_07-0001
  - 0017804_Amendment1_09-0001
  - 0017804_Amendment1_13-0003
  - 0017804_Amendment1_13-0004
  - 0017804_Amendment1_13-0006
  - 0017804_Amendment1_13-0008
  - 0017804_Amendment1_17-0004
  - 0017804_Amendment1_23-0002
  - 0017804_Amendment1_23-0003
  - 0017804_Amendment1_23-0004

- 0017804_Amendment1_23-0007
- 0017804_Amendment1_23-0008
- 0017804_Amendment1_23-0009
- 0017804_Amendment1_23-0021
- 0017804_Amendment1_23-0022
- 0017804_Amendment1_23-0024
- 0017804_Amendment1_23-0025
- 0017804_Amendment1_23-0026
- 0017804_Amendment1_23-0027
- 0017804_Amendment1_23-0029

- Updated Utility Adjustment Schedules:
  - PI 0017804 - U-057-010248-6 CCWSA
  - PI 0017804; Crown Castle UAS
  - PI 0017804; U-057-009422-6 – Zayo
  - PI 0017804; U-057-009763-6 - Sawnee EMC
  - PI 0017804; U-057-010194-6 City of Canton
  - PI 0017804; U-057-013017-6 - AT&T
  - PI 0017804; U-057-015513-6 – Verizon
  - PI 0017804; U-057-019074-6 - GA Power D
  - PI 0017804; U-057-022163-6 – AGL
  - PI 0017804; U-057-022392-6 – Windstream
  - PI 0017804; U-507-016625-6 - Comcast

1. Question: Since project is following GDOT Spec and has a duration longer than 365 Day, can you please confirm that you do intend to utilize the GDOT Asphalt Cement Index?
   Answer: We will not utilize the GDOT Asphalt Cement Index

2. Question: Can you please confirm that all work on this project will have to be performed using the Federal Wage Rates Requirements?
   Answer: Federal wage rates will be required according to the bid documents.

3. Question: Can you please confirm that there will be no DBE Participation requirements?
   Answer: No DBE participation will be required on this project

4. Question: On the SR140 Alignment starting station 41+00 RT to 44+40 RT and Station 42+50 LT to 44+40 LT, existing condition is different than the provided plans. Does contract have to demolish newly completed construction? Please provide clarification.
   Answer: Plan sheets revisions will be provided. A change order will be issued if any changes are necessary.

5. Question: For the Pipe between structure B2.1 & B2, 13 series plan mentions 18" RCP and Drainage profile 22-0007 mentions 24" RCP. Please clarify the correct size to be considered?
   Answer: The proposed pipe is 24”. 13-0003 and 13-0004 will be revised.

6. Question: Please provide the drainage profile for the 18" RCP mentioned at St 40+00 LT to 41+00 LT, between structure D2 & D1 on 13-0006.
   Answer: D1 to D2 is a side drainpipe. No profile will be provided for this pay item.

7. Question: As given on page 4 of 45 of Soil Survey Report, there are findings where in-place moisture contents far above the optimum moisture contents. Which need to be removed and either dried out and replaced or replaced with drier soils. We are requesting clarification that pay item 210-0250 Undercut Excavation, is intended to cover above scope and not just allocation for different reasons?
   Answer: Pay Item 210-0250 is intended to cover unsuitable soil conditions encountered during construction, including areas with excessive moisture content as identified in the Soil Survey Report. Undercut excavation shall be performed at the direction of the Engineer and may not be necessary if the existing subgrade soils are determined to be dry and stable. The quantity provided for Pay Item 210-0250 is an estimated allowance for unsuitable soil conditions and is not limited to a specific cause of unsuitable material.

8. Question: The drainage profile shows a 24” pipe from B2.1 to B2, whereas the mainline drawing indicates an 18” pipe. As per the contract quantities, only one run of 24” pipe is included from B2.1 to B2. Could you please confirm whether the RCP for this section should be 24” or 18”?
   Answer: Refer to question 5 response.

9. Question: 18” side drain is shown on both the Stage 1 and mainline drawings at Orchard Drive; however, the corresponding quantity is not included in the Summary of Quantities. Could you please confirm whether this is a side drain or not?
   Answer: The 18” side drainpipe for Orchard Drive is included in the side drainpipe quantities.

10. Question: The A2–A3 run is not identified as jack-and-bore in the mainline plan or drainage profile. However, the staging plan indicates a jack-and-bore pipe for this location. Please confirm whether the A2–A3 run is intended to be installed using the jack-and-bore method. If so, can pay item to be added?
    Answer: Jack and boring pay item will be added to the bid quantities.

11. Question: C&G 8x30 TP2 is referenced in the Summary of Quantities but is not shown on the plans or typical sections. Could you please clarify where C&G 8x30 TP2 is intended to be installed?
    Answer: TP2 C&G is to be used along Univeter Rd and Orchard Drive. The typical sections will be revised.

12. Question: Driveway Profiles 17, 18, and 19 indicate asphalt driveways; however, the Bid Summary specifies 8" concrete driveways. Could department please clarify which driveway pavement type should be used?
    Answer: The Driveway Profiles sheets will be revised to show concrete, as shown in the quantities.

13. Question: Could you please clarify whether Driveway 20 is intended to be mill and overlay, as shown in the staging plan, or full-depth replacement, as indicated in the summary of quantities?
    Answer: Driveway 20 will be constructed as mill and overlay. The construction plans and bid quantities have been updated in this addendum. The 6 series will be updated in the next plan revision.

14. Question: Could department please provide the utility relocation schedule for each utility owners?
    Answer: The utility relocation schedules will be included in this addendum

15. Question: What are the mill cover requirements for this job?
    Answer: The mill cover requirements will be according to the GDOT spec book.

16. Question: For Orchard Dr, the typical sections show resurfacing, but the plans show full depth. Can you clarify which of these is correct?
    Answer: Orchard Dr will include mill and overlay. The typical section, construction sheets, and quantities will be updated.

17. Question: Please provide the RFB Document for 2026-031.
    Answer: The Request for Bid (RFB) and associated documents can be downloaded from the Georgia Procurement Registry as well as BidNet Direct.

18. Question: Could the department please clarify whether the existing storm drainpipe is to be removed or filled with flowable fill? If flowable fill is required, should the corresponding flowable fill pay items be added?
    Answer: Refer to note 6 on drawing 04-0001.

19. Question: Could the department please clarify whether the 12" GAB is required beneath the curb and gutter, as indicated in the typical section, since it is not shown beneath the curb and gutter in the earthwork cross sections? if so would cross section to be revised?
    Answer: 12” GAB is required beneath the curb and gutter. The cross sections will be revised to show this. This GAB is already accounted for in the quantities.

****END****